

Pre Bid Meeting Clarification against Tender for Designing, Erection, supply, Installation, Testing and Commissioning of Primary Processing Centre for Potato(PPC) at Davas (Deesa), Ratanpur (Bhildi) & Khimana (Kakrej) Or any in Banaskantha

Pre Bid Meeting Date 05.03.2021 at 11.00AM at Banas Dairy, Palanpur

Sr. No.	Tender Page No.	Tender Specification	Bidders Query	Reply by Banas Dairy
1	25	PPC unit should be movable on pneumatic wheel	Only Receiving Hopper with Pre soiler Shall be movable type & on pneumatic wheel	Agreed
2	23	Pre-Sorter/soil remover. 1. No. of Rollers: As per design OEM. - MOC:SS 304	Roller Shall be spiral roller & MOC shall be PU	Agreed
3	23	Pre-Sorter/soil remover.	Pomerisum shall be added to remove soil after pre-soiler.	Pre-Sorter / Soil Remover with Pomerisum belt shall be added for separation of under Size potato & Mud
4	24	Roller inspection table with platform	Roller Inspection table with platform shall be 5000 M Length & 1200 MM Width	Supplier Shall meet the capacity of 20 MTH of individual PPC based on below performance & width & Length shall be as per the OEM Design. Performance of the PPC- 1. No soil Carry over after the Pre-soiler / Pre Sorter. 2. There shall be no carry over of potato having defect likes - Greening, Insect Damage, Mechanical Damage, Bruising, Wet Rot, Dry rot & or any foreign Materials.
5	27	Diversion Conveyor with Bag Holder	Two no's of bag holder is not enough for handling of 20MTH potato	4 No's of bag holder shall be provided with all required attached accessories to meet the 4 bag's filling at a time.

6		Electricals		<p>Banasdairy will provide power & Cable to the Electrical Panel.</p> <p>Connection to the main panel is in the scope of Supplier.</p> <p>Other all electrical & instrumentation is in the scope of Supplier.</p>
---	--	-------------	--	---